

HAZARD / WORK
ACTIVITY ASSESSED

Road Surfacing Plant

Hazard (something with the potential to cause harm)	Risk	W	ho m	ay be	harn	ned	Control Measures		Risk rating after control			
	Severity	Probability	Risk	Operator	Employee	Visitor	Public	Sub-cont		Severity	Probability	Risk
Moving vehicles – striking operatives	4	2	8	х	х		х		Correct signing, lighting and guarding to be set out by fully trained personnel to comply with NRSWA (chapter 8)	4	1	4
Surface plant – striking operatives	4	2	8	Х	х				High vis clothing to be worn at all times and all drivers of machinery to be informed of personnel working in same areas.	4	1	4
Traffic – contact with the public	4	2	8				х		All necessary safety zones and lighting requirements to be incorporated into signing, lighting and guarding as per code of practice.	4	1	4
Noise emissions from vehicles – damage to ears	2	2	4	Х	х				Ear protection to be worn at all times.	1	2	2
Fire / explosions – burns	4	2	8	Х	х			Х	Fire extinguishers to be provided for each item of surfacing plant and all operatives instructed on how to use them.	4	1	4
Moving parts of machines – operatives being caught	4	2	8	х	х				Only trained personnel to operate machines, all other personnel to be kept away from works area.	4	1	4
Pedestrians – injury to	4	2	8				х		All pedestrian walk ways to be clearly signed and guarded and safety zones maintained.	4	1	4
Bituminous substances – contact with	2	3	6	Х	х			х	Safety gloves, safety boots, overalls and masks to be worn.	1	3	3



SAFETY METHOD STSTEMENT

- 1. Traffic control will be planned with Local Authority and Police.
- 2. First-aid, welfare and emergency requirements reviewed, and the information passed to operatives.
- 3. Safe pedestrian routes will be planned as appropriate.
- 4. COSHH, manual handling, PPE & noise assessments will be reviewed, and the information passed to operatives.
- 5. All personnel on site, including visitors to wear high visibility clothing.
- 6. Guards on moving parts must remain in place whilst machines are in motion.
- 7. Tools and equipment should not be left on or in working areas of plant.
- 8. At the end of work machines must be secured.
- 9. Only authorised personnel shall operate machines.
- 10. Safety zones to be set up between plant and moving traffic.
- 11. Continual monitoring of work progress and traffic control systems is required.
- 12. Traffic and pedestrian controls will be checked at the end of each work period and working day.

Health & Safety

Date of first issue:	February 2005	Authorised & published by:	Sharon Kaye					
Content collaborators:	Senior engineering team & MD							
Last review date	2017-06-14							
Revision period (months)	12							

Severity			Probability Risk Rating				
1	No Injury, property damage	1	Very Unlikely	Severity X Probability = 1 to 5	Low	Y – acceptable risk, work can start	
2	Minor Injury	2	Unlikely	Severity X Probability = 1 to 3	LOW	7 – acceptable risk, work carr start	
3	+3 Day Absence	3	Likely	Severity X Probability = 6 to 14	Mod	Y or N - may need further consideration	
4	Major Injury	4	Very Likely	Seventy A Probability = 0 to 14	Med	7 Of N - may need further consideration	
5	Death	5	Virtually Certain	Severity X Probability = 15 to 25	High	N – Unacceptable risk Do not start work	